

**MARYLAND DEPARTMENT OF THE ENVIRONMENT**  
Wastewater Permits Program • Onsite Systems Division  
410-537-3778 • [www.mde.maryland.gov](http://www.mde.maryland.gov)

---

The following list is updated by MDE on a 45-day basis. The results show sieve analysis received within the defined review period that meet either the primary or alternative sand mound specification found in COMAR 26.04.05\*. Contractors, designers, and installers are encouraged to confirm sand sources, availability, and verification of adequacy prior to purchase. Sand suppliers and users are encouraged to continue to submit analysis for each site and as required by permit specification. If sieve analysis is not provided to MDE within each review period noted in the timeline below, the sand supplier will not be listed during that period.

The review period conducted by the Department will last during the typical installation season, from April 1<sup>st</sup> to October 31<sup>st</sup>. If constructing outside of this period, the contractor must confirm sand analysis directly from the supplier, and submit results to the Approving Authority. MDE will post the updated list on the first day of each specified review period. Results must be received prior to the posting date to be listed.

Review Period	Date List is Reposted by MDE	End of Period
1	April 1 <sup>st</sup>	May 15 <sup>th</sup>
2	May 16 <sup>th</sup>	June 30 <sup>th</sup>
3	July 1 <sup>st</sup>	August 15 <sup>th</sup>
4	August 16 <sup>th</sup>	September 30 <sup>th</sup>
5	October 1 <sup>st</sup>	November 15 <sup>th</sup>

\*Primary Specification: Sand effective size is between 0.25 and 0.5 mm, and has a uniformity coefficient of 3.5 or less

Alternative Specification: Sand effective size is between 0.15 and 0.3 mm, has a uniformity coefficient between 4 and 6, contains less than 20% of material larger than 2.0 mm, and contains less than 5% of material less than 0.053 mm

*The companies listed below have reported to MDE that they provide sand that meets either the primary or alternative sand mound specification found in COMAR 26.04.05. This list was prepared by MDE from information known and available at the time of preparation. MDE makes no claim as to its completeness or to the quality of work performed. Inclusion on this list is not to be considered an endorsement by the state of Maryland. MDE recommends that the consumer obtain prices and review company references before entering into agreements with any contractors or service providers.*

**Date Posted: 5/16/2020**

**MARYLAND DEPARTMENT OF THE ENVIRONMENT**

Wastewater Permits Program • Onsite Systems Division

410-537-3778 • [www.mde.maryland.gov](http://www.mde.maryland.gov)

<b>Company Name</b>	<b>Date Analysis Performed</b>	<b>Primary Specification Met (Y/N)</b>	<b>Alternative Specification Met (Y/N)</b>
<b>S.W. Barrick &amp; Sons</b>	<b>4/1/20</b>	<b>Y</b>	<b>N</b>
<b>Keystone Lime Company</b>	<b>4/21/20</b>	<b>N</b>	<b>Y</b>
<b>W.T. Brittingham, Inc.</b>	<b>5/12/20</b>	<b>Y</b>	<b>N</b>